



BLOCK NO	DESCRIPTION	SIZE IN METERS	AREA (SQ. M)	ROOF
01	PRODUCTION BLOCK-1	44.47 18.45 3.6 7.2	728.308	RCC SLAB
02	PRODUCTION BLOCK-2	25.00 14.00 7.2 350.00	350.00	PRE COATED
03	PRODUCTION BLOCK-3	25.00 12.00 4.2 4.2	306.28	OPEN
04	PRODUCTION BLOCK-4	30.00 12.00 13.0 360.00	360.00	PRE COATED
05	GENERATOR ROOM, TRANSFORMER YARD	24.3 8.6 4.5 208.90	208.90	RCC SLAB
06	UTILITY BLOCK	62.0 8.2 5.25 426.40	426.40	PRE COATED
07	RECOVERY SOLVENT DRUMS SHED	13.7 9.2 6.0 126.00	126.00	PRE COATED
08	QC BUILDING-2	14.0 4.85 3.3 67.90	67.90	RCC SLAB
09	BOILER HOUSE 4T/ST	26.30 12.80 4.5 336.58	336.58	AC SHEET
10	DRYING & PACKING-1	23.6 16.4 3.6 387.00	387.00	PRE COATED
11	DRYING & PACKING-2	38.0 12.0 4.2 456.00	456.00	PRE COATED
12	HAZARDOUS WASTE SHED	13.00 8.2 4.2 106.60	106.60	PRE COATED
13	CONF. HALL & CEO ROOM AT GF	15.3 11.0 7.2 168.30	168.30	RCC SLAB
14	WASH AREA SHED	21.9 6.9 4.2 151.00	151.00	PRE COATED
15	WATER SUMP	12.5 10.5 — 131.25	131.25	RCC
16	ENGG. PRODUCTION OFFICE	24.5 9.3 6.0 227.85	227.85	PRE COATED
17	CANTEEN	19.2 16.9 4.0 324.80	324.80	RCC SLAB
17A	TOILETS	20.3 4.3 2.6 87.29	87.29	RCC SLAB
18	FABRICATION SHED	18.3 8.2 4.2 168.38	168.38	PRE COATED
19	SCRAP YARD	15.0 4.0 3.0 60.00	60.00	MS SHEET
20	DRY HCL PLANT	5.9 5.0 2.9 29.00	29.00	RCC SLAB
20 & 21	R.M. STORE & BONDED STORE	32.5 39.30 6.0 1434.38	1434.38	PRE COATED
22	SOLVENT DRUMS STORE	54.0 11.0 5.545 594.00	594.00	PRE COATED
23	SOLVENT STORAGE TANKS	23.0 16.5 4.5 379.50	379.50	PRE COATED
24	ADMIN OFFICE & PERSONAL DEPT.	8.60 7.2 3.6 61.92	61.92	RCC
24A	PARKING SHED	36.0 4.0 2.1 144.00	144.00	PRE COATED
25	SECURITY OFFICE & CYCLE SHED	27.0 4.5 2.1 121.50	121.50	PRE COATED
26	EFFLUENT TREATMENT PLANT	— — — 2583.142	2583.142	—
27	BLOCK-3 MCC3 PANEL ROOM	13.5 6.3 4.0 85.00	85.00	R.C.C. SLAB
29	ELECTRICAL PANEL ROOM FOR SOLVENT STORAGE YARD	8.50 4.2 3.6 36.70	36.70	R.C.C.
30	WORKERS QUARTERS	39.0 8.0 4.2 351.00	351.00	A.C. SHEET
31	ENGG. STORE & TRAINING HALL	29.3 5.7 4.2 167.00	167.00	R.C.C. SLAB
32	DM WATER PLANT	15.5 11.5 4.0 178.25	178.25	PRE COATED
33	CYLINDER STORAGE SHED	20 10.23 6.0 204.60	204.60	PRE COATED
34	DS TANKS	13.5 9.5 — 128.25	128.25	—
35	RO PLANT	14.3 9.3 4.5 132.99	132.99	PRE COATED
36	DINING HALL	22.5 9.0 4.2 202.50	202.50	PRE COATED
37	R.M. STORE-2	30.0 12.0 6.0 360.00	360.00	PRE COATED
38	MEE PLANT 1001	18.0 7.3 4.581 131.40	131.40	—
39	MEE PLANT 1002	12.0 7.3 4.581 87.90	87.90	—
40	BLOCK-1 DAY MATERIAL STORAGE SHED	15.50 8.0 4.2 124.00	124.00	PRE COATED
41	DETOXIFIED CONTAINERS SHED	18.3 9.2 4.2 168.32	168.32	MS SHEET
42	HAZARDOUS SHED-2	18.2 9.3 4.2 168.36	168.36	MS SHEET
43	RECOVERY PLANT	16.0 10.0 4.2 160.00	160.00	MS SHEET
44	STORM WATER COLLECTION TANK	21.0 11.3 — 237.30	237.30	R.C.C.
45	BULK CHEMICAL	17.5 6.00 — 105.00	105.00	MS SHEET
46	WEIGH BRIDGE	— — — —	—	—
49	EQUIPMENT YARD	29.5 28.50 — 840.75	840.75	—

03	PRODUCTION BLOCK - 3A	32.0 10.0 13.5 360.00	RCC
04	PRODUCTION BLOCK - 4D	30.0 4.5 8.0 135.00	OPEN
09A	NEW BOILER HOUSE	16.97 11.5 14.0 195.15	PRE COATED
25A	PARKING SHED	81.0 4.5 2.1 364.50	PRE COATED
28	STORE (BLOCK-3 AREA)	12.0 6.6 4.2 83.00	PRE COATED
39	BLOCK-3 DAY MATERIAL STORAGE SHED	13.5 9.0 4.2 121.50	PRE COATED
47	33KVA SUB STATION	30.0 20.0 — 600.00	—
48	WATER SUMP	20.0 13.0 — 260.00	—
50	PRODUCTION BLOCK-5	78.4 40.0 14.7 10739.70	MS SHEET
51	STORM WATER COLLECTION STORAGE TANK	6.00 6.00 — 36.00	—
52	SECURITY & TIME OFFICE	13.0 4.00 5.0 52.00	MS SHEET
53	DG ROOM	15.0 6.00 6.0 90.00	MS SHEET
54	FIRE HYDRANT SYSTEM	30.0 10.00 — 300.00	—
55	PCC ROOM	15.00 6.00 5.0 90.00	MS SHEET
56	C-1301,C-1302,C-1305	15.0 15.0 — 225.00	—
57	CANTEEN	4.4 3.5 5.0 15.40	MS SHEET
58	TOILETS	3.80 3.50 4.5 13.30	MS SHEET
59	NON EFFLUENT CHEMICAL STORAGE SHED	15.0 6.00 8.0 90.00	MS SHEET
60	NON CLASSIFIED CHEMICAL STORAGE SHED	40.0 20.0 8.0 800.00	MS SHEET
61	QC BUILDING	25.0 15.0 13.5 1125.00	RCC SLAB
62	BIOLOGICAL TREATMENT PLANT	33.6 33.5 — 1125.60	—

TOTAL LAND AREA: 64.75Acres (OR) 262062.16 Sqm
GREENERY AREA (38.68%) 101376.24 Sqm
TOT LOT AREA (10.00%) 26169.45 Sqm
PARKING AREA (22.00%) 7441.06 Sqm
OPEN & ROADS AREA 99011.20 Sqm

EXISTING BUILTUP AREA 16401.85 SQM
PROPOSED BUILTUP AREA 17421.15 SQM
TOTAL BUILTUP AREA 33823.00 SQM

10% MORTGAGE AREA ON PROPOSED BUILT UP AREA - 1742.115 SQM
PROVIDED IN BLOCK NO 60 AND 61 — 1925 SMTS.

EXISTING H.P: 5619.00
DELETION H.P: —
PROPOSED H.P: 2611.30
TOTAL H.P 8230.30

BOUNDARIES:
NORTH - N.H-65 ROAD & OTHERS LAND
SOUTH - CANAL
EAST - BALRAM - VASARAM TANDA & OTHERS LAND
WEST - NALA & OTHERS LAND

SCALE 1:1000
GENERAL NOTES
1) ALL DIMENSIONS ARE IN MM & LEVEL IN Mtrs ONLY
EXISTING ☐ PROPOSED ☐ DELETION ☐
SITE LAYOUT
ENGINEER SIGN:
RELEASED FOR: ☐ REVIEW ☒ APPROVAL ☐ CONSTRUCTION
SIGN OF OCCUPYER:
For M/s. Suven Pharmaceuticals Limited
Authorised signatory:
SAI RAM DESIGNS & DRAFTING
HYDERABAD-500 043, TELANGANA (S)
E-mail: sairammm@gmail.com
CELL-9949050316, 8978880316